

San Joaquin River Restoration Program



Water Management Technical Feedback Meeting

Visalia, CA

March 16, 2018



Agenda

- Introductions
- 2017 In Review
- 2018 Outlook
- Water Management Goal Project Status
- Stakeholder Feedback
- Break
- Lecture Series: SCCAO Water Supply
- 2018 Meeting Schedule
- Adjourn




2017 IN REVIEW



2017 Hydrology

- 4.395 MAF – 2nd wettest year since 1900
- 240% of average runoff, 220% of average snowpack
- Higher proportion of rain:snow
- High snow levels due to warm storms
- Airborne Snow Observatory data used in 2017 to guide blending of DWR & NWS forecasts.
- Since early June, held in-house projection to 4.406 MAF

2017 Restoration Year Type



2017 Restoration Schedule

- Wet restoration year type
 - 673 TAF Friant Dam release / 557 TAF @ GRF
 - 150-300 cfs limit below Sack Dam in Spring & Summer
 - 189 TAF scheduled / 367 TAF Unreleased Restoration Flows (URFs)
 - Of the 189 TAF scheduled Restoration Flows, 97 TAF of those were flood flows.



2017 Restoration Schedule

- URFs
 - 364.967 TAF Gross Tier 1 (346.719 TAF Net)
 - \$20/AF – no refunds for undelivered water
 - Not fully schedulable, tied to default hydrograph
 - Deliver by end of Uncontrolled Season
 - 2.491 TAF Gross for last minute URF Exchange
- Flood flows through July 21
 - Issue of Flood flows not meeting RA Recommendation at Sack Dam (0 cfs below Sack Dam)
 - Highlighted need for greater clarity in Restoration Flow Guidelines pertaining to flood flows

2017 Restoration Schedule

- Fall Pulse released two periods
 - 1,256 AF as early September pulse (within Flexible Flow Period)
 - Remainder of Fall pulse moved to February (outside of Flexible Flow Period, applied Water Supply Test)
 - 2,491 AF at end of year put into URF Exchange



2017 Restoration Schedule

- Gravelly Ford Accounting
 - Holding Contracts less than Exhibit B for over 2 months after flood flows
 - Inconsistency/Discrepancy with Settlement / Restoration Flow Guidelines on how to account
 - Feedback sought from Settling Parties and RA
 - Implemented interim procedure for accounting, use GRF flows, but adjust for “residual flood flows”



2018 OUTLOOK



2018 Allocation

- January 20: 20/80 blending and 75% exceedance produced **741 TAF** Natural River Forecast
 - Dry
 - 171.178 TAF at Gravelly Ford
- February 16: 30/70 blending and 90% exceedance produced **525 TAF** Natural River Forecast
 - Critical-High
 - 70.919 TAF at Gravelly Ford
- March 16: 40/60 blending and 75% exceedance produced **928 TAF** Natural River Forecast
 - Dry
 - ~ 195 TAF at Gravelly Ford



2018 Forecasting Efforts

- Joint Forecasting
 - SJRRP and SCCAO meeting weekly to review data, blend DWR and NWS forecasts, and direct scientific efforts
 - Apprentice training
 - Staff supporting other efforts (DWR, ARS, ASO)
- NASA ASO
 - First flight March 4-5 for portion of watershed
 - Funding constrained, difficulty of getting \$ to NASA
 - Early April and May flights planned to coincide with snow course sampling



2018 Forecasting Efforts

- **Agricultural Research Service**
 - iSnoBal model to track snowpack between ASO flights
 - Biweekly reports
 - Model driven by high-resolution forecast to melt and accumulate snow between ASO flights
 - Model development proceeding well
- **Univ of Colorado Boulder / NASA**
 - Satellite based snow-cover product
 - Monthly reports (perhaps biweekly in future)
 - Seeking integration with NASA ASO, ARS iSnoBal



WATER MANAGEMENT GOAL PROJECT STATUS



Madera Canal Projects

Low Flow Valve

- Valve installed in August 2017
- Valve Testing completed February 2018

Madera Canal Capacity Restoration

- Selected measures to proceed as separate projects
 - CWD Improvements
 - Fresno River Diversion

FKC Capacity Restoration

- Original project formulation infeasible with authorized funding
- Working with Friant Contractors to reformulate alternatives and focus on subsidence area
- Seeking additional authorizations and funding sources to implement a more comprehensive solution

Groundwater Financial Assistance

Tulare ID - Cordeniz Basin

- 80-acre basin
- Groundbreaking: December 2015
- Complete: Summer 2019

Shafter-Wasco ID - Madera Avenue Intertie

- 270-acre recharge basin at Kimberlina Rd.
- Recharge ponds complete
- Flood water turned out into them in 2017

Groundwater Financial Assistance

Porterville ID - In-Lieu Project

- Connects two service areas (2,170 acres) to surface supplies from the Wood-Central Ditch and Friant-Kern Canal
- Construction started August 2017

Pixley ID - Joint Groundwater Bank

- 560-acre bank; 4.5 mile pipeline; new FKC turnout
- FONSI signed December 28, 2017
- Initiation of construction pending CEQA litigation



Recapture & Recirculation

2017 Recapture – 26,000 AF

- 17,000 AF at Patterson and Banta-Carbona Irrigation District facilities
- 9,000 AF at Mendota Pool

R&R Plan

- Delta Recapture pilot plan, Draft 2017
- Recirculation Chapter update – workshop tentatively planned for summer 2018



LONG-TERM RECAPTURE AND RECIRCULATION OF RESTORATION FLOWS EIS/R



Overview

- Administrative Draft EIS/R Review
- Alternatives Under Consideration
- Baselines Evaluated in the EIS/R
- Preliminary Findings
 - Resource Areas Potentially Affected by Operations
 - Resource Areas Potentially Affected by Construction
- Next Steps and Schedule

2nd Administrative Draft Review

- Administrative Draft EIS/R will be shared with Settling Parties and Cooperating Agencies for review and input
- Feedback received will be incorporated into the Public Draft EIS/R scheduled for completion later this year

**San Joaquin River Restoration
Program Long-term Recapture and
Recirculation of Restoration Flows
Project**

Second Administrative Draft
Environmental Impact Statement/ Report



March 2018

EIS/R Alternatives

- Alternative 1 - No Action/No Project
- Alternative 2 – Continue Existing Temporary Recirculation Actions
- Alternative 3 – Maximize Use of Existing Facilities
- Alternative 4 – Expand Existing Facilities
- Alternative 5 – Construct New Facilities

**San Joaquin River Restoration
Program Long-term Recapture and
Recirculation of Restoration Flows
Project**

Second Administrative Draft
Environmental Impact Statement/ Report



March 2018



Baselines Evaluated in the EIS/R

- Existing Conditions – reflects conditions at the time of the CEQA NOI which includes:
 - Elements of the Settlement evaluated at a project level in the PEIS/R that are currently underway
 - Unreleased Restoration Flows that have ranged annually from zero to the full Restoration Allocation
 - Restoration Flows below Sack Dam at 300 cfs
 - Recapture in the Restoration Area and at the Delta Pumps
 - Recirculation of recaptured Restoration Flows

Baselines Evaluated in the EIS/R

- No Action/No Project Alternative – reflects reasonably foreseeable future conditions in the absence of this project which includes:
 - All elements of the Settlement evaluated at a project level in the PEIS/R under Alternative C1
 - Unconstrained release of Restoration Flows
 - Recapture in the Restoration Area and at the Delta Pumps
 - Other elements of the SJRRP that have made substantial progress towards implementation

Preliminary Findings – Operations Effects

- Long-term operations-related impacts evaluated under all of the alternatives
- Resources with long-term effects identified include:
 - Air Quality
 - Bio Resources – Fisheries
 - Bio Resources – Veg. & Wild.
 - Climate Change
 - Groundwater
 - Hydrology – Surface Water
 - Hydrology –Water Quality
 - Land Use and Ag Resources
 - Noise
 - Recreation
 - Utilities and Service Systems

Preliminary Findings – Construction Effects

- Short-term construction-related impacts limited to Alts 4 & 5
- Resources with construction impacts requiring mitigation include:
 - Air Quality
 - Bio Resources – Fisheries
 - Bio Resources – Veg. & Wild.
 - Climate Change
 - Cultural Resources
 - Geo and Soils
 - Land Use and Ag Resources
 - Noise
 - Paleontological Resources
 - Hazardous Materials
 - Traffic and Transportation
 - Utilities and Service Systems
 - Visual Resources

Next Steps and Schedule



Stakeholder Outreach



FKC Reverse Flow Pump-Back Project



STAKEHOLDER FEEDBACK



Questions?



BREAK



LECTURE SERIES



NEXT MEETINGS

Next Meetings

Date	Location
May 2018	Visalia
Summer 2018 workshop	TBD
September 2018	Sacramento